



# DEEP SPACE EXPLORATION SYSTEMS

**EXPLORATION SYSTEMS DEVELOPMENT UPDATE**


**NASA ADVISORY COUNCIL – MARCH 26, 2018**

**BILL HILL, DEPUTY ASSOCIATE ADMINISTRATOR  
EXPLORATION SYSTEMS DEVELOPMENT**

**MARSHALL SMITH, DIRECTOR, CROSS-PROGRAM SYSTEMS INTEGRATION  
EXPLORATION SYSTEMS DEVELOPMENT**

2

December Month End Data






# DRAFT EM-2 IMMS



NAC - March 26, 2018

3

Last update: 02/08/18




# EM-1 SE&I SUMMARY SCHEDULE



NAC - March 26, 2018

4

Last update: 02/01/18




# EM-1 SE&I SUMMARY SCHEDULE



NAC - March 26, 2018

5

Last update: 02/01/18



# SE&I INTEGRATED ISSUES



NAC - March 26, 2018

6

Critical Integrated Issue Topic	Action	Current Status
<b>Integrated Loads and Guidance, Navigation and Control (GN&amp;C)</b>	Ensure that structural math models are properly verified and validated in the most efficient manner possible and support the needs of EM-1 loads assessments, GN&C algorithm design requirements, and to collect data for crewed EM-2 flight.	<ul style="list-style-type: none"><li>Enterprise has approved three modal tests designed to incrementally characterize the integrated system: Mobile Launcher (ML)-modal, Partial Stack Modal Test (PSMT), and Integrated Modal Test (IMT)</li><li>Continuing to evaluate schedule for math model characterization efforts including structural tests, loads and GN&amp;C analyses, and Best Model Estimate (BME)/Flight Dynamics Risk Assessment (FDRA)</li></ul>
<b>Orion Simulator</b>	Fully develop and submit for approval a contingency plan to use the Orion Simulator should the actual ESM/Orion be later than planned to KSC	<ul style="list-style-type: none"><li>Simulator requirements approved at JICB.</li><li>Developing plan forward with list of key decision dates for implementation, will bring to JICB.</li></ul>
<b>Enterprise Verification and Validation</b>	Ensure that the Enterprise Verification and Validation (EV&V) activities will not delay the launch	<ul style="list-style-type: none"><li>Planning V&amp;V checkpoint in June 2018 to finalize ESD, ITT, and Program expectations in integrated V&amp;V execution and reporting</li><li>Developed integrated verification burndown metrics</li><li>Developed approach to interface verification</li><li>Engaging in Modeling &amp; Simulation (M&amp;S) certification effort to ensure overall V&amp;V schedule is met (CPIT creating ad hoc M&amp;S cert team)</li></ul>

# SE&I INTEGRATED ISSUES



NAC - March 26, 2018

7

Critical Integrated Issue Topic	Action	Current Status
<b>Core Stage Assembly, Integration and Test (AI&amp;T)</b>	Increase SE&I focus and engagement on Core Stage (CS) AI&T issues that could impact the EM-1 integrated schedule (e.g. late hardware delivery impacts to Green Testing schedule and subsequently to CS, SLS and ESD verification)	<ul style="list-style-type: none"><li>Core Stage remains critical path driver for SLS; critical path is through Engine Section Integration</li><li>Schedule challenges due to late parts &amp; work instruction redlines</li></ul>
<b>Green Run Testing</b>	Increase SE&I focus and engagement on Green Run planning and execution that could impact the EM-1 integrated schedule	<ul style="list-style-type: none"><li>Schedule is success-oriented; assumes minor traveled work from MAF, limited weather delays; nominal margin for non-conformances or first time operations</li><li>Evaluating potential traveled work between SSC and KSC</li></ul>
<b>ESA Service Module (ESM)</b>	Increase SE&I focus and engagement on ESM issues that could impact the EM-1 integrated schedule	<ul style="list-style-type: none"><li>Working closely with Orion to understand key schedule drivers that may affect the Enterprise</li></ul>
<b>Vehicle Assembly, Integration and Test (AI&amp;T)</b>	Oversee and manage the EM-1 AI&T flow	<ul style="list-style-type: none"><li>Working with EM-1 flow director to understand schedule and identify and pursue opportunities</li></ul>
<b>Integrated Software</b>	Ensure that all major software development areas are integrated and ready to support EM-1	<ul style="list-style-type: none"><li>Working to ensure that software content, emulator capability, OMRS/LCC dependencies, and testing schedules are aligned</li></ul>

# SE&I INTEGRATED ISSUES



NAC - March 26, 2018

8

Critical Integrated Issue Topic	Action	Current Status
<b>Pad Stay Time</b>	Resolve hardware problems and requirements related to pad stay time across the Enterprise	<ul style="list-style-type: none"><li>• Discussing load spectrum; Orion hardware testing in progress; cleaning up requirements</li></ul>
<b>Fracture Control</b>	Develop list of hardware with fracture control problems or where testing is costly in comparison to the risk reduction provided	<ul style="list-style-type: none"><li>• Working with Orion and SLS programs and chief engineers to collect list of hardware with fracture control problems</li><li>• Collecting list of EM-1 variances to fracture control requirements</li></ul>
<b>Integrated Trajectories</b>	Review trajectory analysis plans and ensure trajectories are ready to support Flight Readiness Analysis Cycle (FRAC) and final flight trajectory target generation	<ul style="list-style-type: none"><li>• Working through delivery issues</li><li>• Kicking off FRAC-0 dry run</li><li>• Will set Groundrules and Assumptions (GR&amp;A) for Final Mission Analysis (FMA)/FRAC-0 in late March</li></ul>
<b>Booster Throat Plug Debris</b>	Assess and develop best approach to mitigate Booster Throat Plug Debris Impact to RS-25 Debris Risk	<ul style="list-style-type: none"><li>• Assessing Booster water nozzle down angle</li><li>• Discussing potential water-debris tests</li><li>• Looking at Booster nozzle throat plug redesign</li></ul>
<b>Payloads</b>	Assess and recommend best approach for payload process: approval, requirements, development and verification necessary for co-manifested, secondary and primary (cargo) payloads	<ul style="list-style-type: none"><li>• Team reviewing existing body of work regarding payloads</li></ul>
<b>Mobile Launcher Stress</b>	Resolve Mobile Launcher (ML) stress concerns, while minimizing impacts to EGS schedule and risks to flight vehicles	<ul style="list-style-type: none"><li>• EGS proceeding with design for extensible columns underneath the ML, similar to those used by Apollo</li><li>• JLT performing loads assessment, will bring to JICB</li></ul>





## **Interim Cryo-Propulsion Stage (ICPS) Umbilical Loads:**

- Initial ICPS integrated loads over hardware design loads

## **Launch Availability:**

- Launch opportunities are limited; looking for improvements

## **Communication uplink for EM-2 EUS:**

- SLS decided not to include uplink capability for EM-2 Exploration Upper Stage (EUS) because it did not provide sufficient benefit with respect to cost

## **Block 1B Loads Exceed Orion Design Loads**

- Block 1B Design Analysis Cycle (DAC) 1R section loads and other critical interfaces show increases over the Orion design baseline

## **Block 1B Vehicle Damper System Location**

- Need to finalize location of vehicle damper system final location


# LOADS MODEL VERIFICATION AND VALIDATION BUILDING BLOCK APPROACH



NAC - March 26, 2018

1010

- Test-validated Element & Program structural dynamics models are used in building block approach to assemble integrated flight models
- Element & Orion static influence coefficient and modal tests are used to correlate individual element and program models and quantify the modeling uncertainty
- Integrated system level testing at KSC further quantifies the interfaces and interactions between individual elements and programs to reduce the modeling uncertainty
  - ML only Modal Test
  - Partial Stack Modal Test (PSMT)
  - Integrated Modal Test (IMT)



# CORE STAGE ENGINE SECTION STA



NAC - March 26, 2018

11



## 4619 Test Stand Capabilities:

- Over 3.5M Pounds applied Vertically
- Over 1M Pounds applied Horizontally
- Isolated from High Bay Concrete
- LN2 Cryogenic Delivery System

## SLS Engine Section Testing:

- Loads over 4.0M Pounds
- 55 Load Lines (up to 18" Bore Cylinders)
- Thermally Conditioned (LH<sup>2</sup> Simulator)
- Over 3200 Measurements

## Test Stand Information:

- Area 50' x 45'
- Height 60'

## Schedule Milestones:

- **2/8/18 - All Qual and Margin Testing Complete**
  - Structure passed Qual testing beyond Limit Loads.
  - Tested beyond liftoff LL at Booster interface with no structural failure noted.
- 7/1/19 - Correlated model delivery to NASA L2

# CORE STAGE LIQUID HYDROGEN (LH2) STA



NAC - March 26, 2018

12

## Test Stand 4693

### Construction

- Twin tower design bridged by movable crosshead
- Built atop original Saturn V F1 engine stand foundation
- 17' thick concrete w/835 tons embedded steel foundation
- 48 feet x 48 feet x 221 feet tall

### Static Load capability

- 3.25M lbs of downward axial compression force
- 2.20M lbs of upward axial tension force
- 340k lbs of north-south & east-west shear force
- 817.5M in-lbs of bending moment force
- 30k lbs tangential & 22k lbs radial force available at both 100' & 150' approx. elevations

### Fluids


- 450k gals stored cryogenic liquid nitrogen (LN<sub>2</sub>)
- Gaseous nitrogen pressurization/purge gas
- Gaseous high-purity air (HPA) & helium

### Instrumentation

- 3400+ strain gauges
- 270 deflections measurements
- 130+ temperature & pressure sensors
- 8 microphones & 24 video cameras
- 76 load measurements

### Test Systems

- 160 ton center hoist / 2 ton jib hoists (4)
- Test article flood lighting
- Mast climbing work platforms w/approx. 150' max elevation
- Lightning protection & electrical grounding grid
- Generator backed up 110v/208v/480v power
- 42' x 50' concrete mounting pad w/threaded hole anchor grid



### LH2 Test Schedule Milestones

- 09/15/18 - Test article at TS4693
- 10/22/18 - T/A installed in stand
- 02/20/19 - Test Readiness Review
- 03/08/19 - Test Start
- 03/29/19 - CS GR Test Cases Complete
- 06/07/19 - CS DCR Test Cases Complete
- 7/1/19 - Correlated model delivery to NASA L2



# CORE STAGE INTERTANK STA



NAC - March 26, 2018

13



## 4619 LTA Facility Capabilities:

- Built in the 1960's
- Moveable Crosshead
- 30M Pound Loading Capacity
- 27' Thick Concrete Floor to React Loads

## SLS Intertank Testing:

- Expect Loads over 11 M Pounds
- Thermally Conditioned
- Over 2200 Measurements Planned
- 48 Tests are Planned
- Additional "Margin Testing" planned following certification test series.

## Test Configuration Facts:

- Area 60' x 60'
- Height ~62'
- Over 2M Pounds of Structural Steel

## Schedule Milestones:

- [3/3/18 - Article at 4619](#)
- 9/6/18 - Test Readiness Review
- 10/10/18 - Test Cases Complete for CS WDR
- 10/15/18 - Test Cases Complete for CS GR
- 1/3/19 - Test Cases Complete for DCR
- 7/1/19 - Correlated model delivery to NASA L2



Test Configuration

# CORE STAGE LIQUID OXYGEN (LOX) STA



NAC - March 26, 2018

14



## 4697 Facility Capabilities:

- Completed in 2016 to Support SLS Program
- Concrete Floor to React Loads
- Outdoor Test Facility
- Cryogenic System ( $LN^2/LH^2$ )

## SLS LOX Tank Testing:


- 34 Load Lines Apply Liftoff & Ascent Loads
- LOX Tank Thermally Conditioned with  $LN^2$
- Bonded Heat Strips will Simulate SRB Heating
- Over 2500 Measurements Planned
- 24 Tests are planned
- Additional “Margin Testing” planned following certification test series

## Test Stand Information:

- Area ~36' x ~36'
- Height ~82'

## Schedule Milestones:

- 11/10/18 - [Article at 4697](#)
- 2/7/19 - Test Readiness Review
- 6/12/19 - Test Complete





# ICPS INTEGRATED STRUCTURAL TEST



NAC - March 26, 2018

15

- Test performed February to May 2017
  - Orion Spacecraft Adaptor
  - Interim Cryo Propulsion Stage (ICPS)
  - Launch Vehicle to Stages Adaptor (LVSA)
- The test article successfully withstood all limit, ultimate, and margin load cases with no signs of detrimental deformation, rupture, or collapse
  - Obtained dynamic characterization
  - Load tested article to ultimate load levels
  - Loaded ICPS to beyond limit load (margin tests)
  - Obtained compartment acoustic characteristic



**ICPS Test Article  
in Test Stand**

# SLS STA TESTING SUMMARY




NAC - March 26, 2018

16

- ✓ Complete Integrated Spacecraft and Payload Element Structural Test - April 2017
- ✓ ES Structural Test Article (STA) ready to ship - April 2017
- ✓ Core Stage Pathfinder Delivered - October 2017
- ✓ ES STA structural test complete - November 2017
- ✓ IT Test Facility ready - November 2017
- ✓ IT STA ready to ship - February 2018
- LH2 STA ready to ship - August 2018
- LO2 STA ready to ship - September 2018
- IT STA structural test (Wet Dress Rehearsal Run) begin - October 2018
- LO2 STA structural test (Design Certification Review Run) begin - January 2019
- LH2 STA structural test (Green Run) begin - March 2019



**Core Stage  
Pathfinder  
Delivered**




**Intertank STA at MAF**



**ISPE STA & Stand -  
Testing Started**



**Engine Section STA Stand**



**LH2 Tank STA Stand**



**LO2 Tank STA Stand**



**Intertank STA Stand**

(Next)

**Stands:**



**ICPS/LVSA  
Stand  
Ready**



**ES STA  
Stand  
Ready**



**LH2 Stand  
CoF  
complete**



**LOX  
Stand CoF  
Complete**



**Intertank  
STA Stand  
Ready**

**STAs  
and  
Testing:**



**ICPS/LVSA  
STA  
Complete**



**Start  
ICPS/LVA  
Testing**



**ES STA  
Complete**



**LH2 STA  
Complete**



**LO2 STA  
Complete**



**IT STA  
Complete**

IT= Intertank  
ES = Engine Section  
ISPE = ICPS/LVSA  
LVSA = Launch  
Vehicle Stage  
Adapter



# ORION STRUCTURAL QUALIFICATION



NAC - March 26, 2018

17

## Crew Module (CM) Structural Test Article (STA)

- ✓ Completed stiffness load test - September 2017

## European Service Module (ESM) STA

- ✓ Completed ESM STA - August 2017

## Launch Abort System (LAS) STA

- ✓ Completed load test - August 2017

## Combined

- ✓ CM/SM/LAS assembly completed - December 2017
- ✓ Combined stack testing – modal completed - January 2018
- Combined stack testing - acoustic - May 2018
- Combined stack testing- pyro shocks - May 2018
- Forward Bay Cover jettison tests - October 2018
- EM-1 prerequisite tests complete - February 2019



*Configuration 9 Test*



*Configuration 3 Test*

# ORION TESTING SCHEDULE



NAC - March 26, 2018

18

## PREPARING ORION FOR FLIGHT



### PRESSURE TESTING

Pushing and pulling with pressure that equates to 140% of the maximum expected loads during missions ensures the spacecraft structures withstand intense loads at launch and re-entry.



### MODAL TESTING

With more than 20,000 parts making up Orion's Service Module alone, modal tests are needed to evaluate how all of the spacecraft components hold up to vibration, especially at connection points.



### JETTISON TESTING

These tests will mimic deployment mechanisms required to jettison the Forward Bay Cover to ensure components can endure the shock levels expected during flight.



### LIGHTNING TESTING

This test will evaluate potential flight hardware damage if the flight vehicle is exposed to a lightning strike prior to launch.



### ACOUSTIC TESTING

Orion will need to withstand incredible forces during missions. Blasting the structures with sound waves simulates the vibrating rumble reaching more than 150 decibels at launch.



### PYROTECHNIC TESTING

Shock tests recreate the powerful pyrotechnic blasts that are needed for critical separation events during flight, such as the launch abort system separating from the crew module after a successful launch.

2017

2018

2019




# EM-1 SE&I SUMMARY SCHEDULE



NAC - March 26, 2018

19

Last update: 02/01/18




# INTEGRATED VEHICLE MODAL TESTS



NAC - March 26, 2018

20

- The program has approved three modal tests designed to incrementally characterize the Mobile Launcher (ML) and SLS hardware





# BEST MODEL ESTIMATE (BME) & FLIGHT DYNAMICS RISK ASSESSMENT (FDRA) OVERVIEW



NAC - March 26, 2018

21


- Best Model Estimate and Flight Dynamics Risk Assessment  
BME/FDRA approach will develop a suite of potential modal testing results to allow easier assessment of test results
  - Thousands of model dispersions are created from the pre-test (PSMT, IMT) models
  - Each dispersion is compared to the modal test results to determine which one best matches the test (BME)
  - The BME is projected from the test configuration to the flight configurations
  - GN&C will take the BME flight models and run a stability assessment
  - Loads will use the Orion and SLS element load transformation matrices corresponding to the pre-test models to perform a quick loads risk assessment
  - Final risk assessment will be presented at FRR

# BACKUP





## Cross Program System Integration (CSI) Accomplishments – Last Quarter



- Established SE&I and Integrated Mission Production and Activities Schedule (IMPAS) summary schedules to form an ESD overall schedule complement with the Integrated Mission Milestone Summary (IMMS) (Nov)
- Formed 14 SE&I teams to address critical integrated issues (Nov)
- HEO Exploration Requirements HEOMD-004 approved (Feb)
- Completed Engine Section Structural Testing (Nov)
- Completed Underway Recovery Test (URT)-6 (Jan)
- Completed 14 Integrated Comm/Network tests to verify functionality and data flows (Feb)
- ESD Functional & Operational Capabilities Closure Report (FCR) Baseline Release (Nov)
- Completed ascent loads for Verification Analysis Cycle (VAC)-1R Coupled Loads Analysis (CLA) (Jan)
- Completed VAC-1R flex models (Jan)
- Delivered VAC-1 aerothermal environments for new Outer Mode Line Protuberances
- Delivered EM-1 off-nominal loads for element and cross-program assessment (Jan)
- Block 1B Design Analysis Cycle (DAC)-2 shared compartment thermal environment analysis completed
- Closed CPIT top issue: Interim Cryo-Propulsion Stage (ICPS) Umbilical Loads (Jan)
- Delivered EM-1 Launch and Landing Mission Table for recovery planning on launch dates through December 2020 (Nov)
- Performed GSDO Advanced Hardware LCS Emulator (GAHLE) network testing in ITL (Nov)
- Performed Ground to Flight Application Software (GFAS) testing in the Integrated Test Lab (ITL) (Dec)
- Updated emulator software in Customer Avionics Interface Development and Analysis (CAIDA) lab to SLS FSW14S6 (Dec)
- Tri-Program emulator technical interchange meeting (Feb)

# ACRONYMS AND ABBREVIATIONS



NAC - March 26, 2018

24





Acronym	Definition
AA	Ascent Abort
ACM	Attitude Control Motor
AI&T	Assembly, Integration, and Testing
AIS	Aft Interstage
AM	Abort Motor
ASEU	Aft Skirt Electrical Umbilical
ASPU	Aft Skirt Pneumatic Umbilical
ATLO	Assembly, Test, and Launch Operations
ATP	Authority to Proceed
BFS	Backup Flight System
C&DH	Command and Data Handling
CAA	Crew Access Arm
CM	Crew Module
CMA	Crew Module Adapter
CMASS	Crew Module Ammonia Servicing Subsystem
CoF	Construction of Facilities
CS	Core Stage
CSFSU	Core Stage Forward Skirt Umbilical
CSITU	Core State Intertank Umbilical
CSS	Consumable Storage System
CT	Crawler Transporter
DFAT	Direct Field Acoustics Test
ECLSS	Environmental Control and Life Support System
ECS	Environmental Control System
ECU	Engine Controller Unit
EGS	Exploration Ground Systems
EM	Exploration Mission
EMI/EMC	Electromagnetic Interference and Electromagnetic Compatibility
ES	Engine Section
ESA	European Space Agency
ESD	Exploration Systems Development
ESM	European Service Module
EUS	Exploration Upper Stage
FCAS	Flight Controller Application Software
FCV	Flow Control Valve
FDIR	Fault Detection Isolation& Recovery
FIL	Fillet Panel
FM	Flight Model
FS	Forward Skirt
FSS	Fixed Service Structure
FSW	Flight Software

Acronym	Definition
FWD	Forward
GFAS	Ground/Flight Application Software
GFAST	Ground/Flight Application Software Team
GHe	Gaseous Helium
GN2	Gaseous Nitrogen
GNC	Guidance, Navigation, and Control
GO2	Gaseous Oxygen
GRAS	Green Run Application Software
GRC	Glenn Research Center
GSE	Ground Support Equipment
HB	High Bay
HF	Hot Fire
IBR	Integrated Baseline Review
ICPS	Interim Cryogenic Propulsion Stage
ICPSU	Interim Cryogenic Propulsion Stage Umbilical
IOPSS	Ignition Over Pressure and Sound Suppression
IPO	Initial Power On
	Integrated Spacecraft and Payload Element
ISPE	(ICPS/LVSA)
IT	Intertank
ITL	Integrated Test Laboratory
JM	Jettison Motor
KCCS	Kennedy Complex Control System
KSC	Kennedy Space Center
LAS	Launch Abort System
LEO	Low Earth Orbit
LETF	Launch Equipment Test Facility
LH2	Liquid Hydrogen
LO2	Liquid Oxygen
LOX	Liquid Oxygen
LVSA	Launch Vehicle Stage Adapter
MAF	Michoud Assembly Facility
MATA	Motor Adapter Truss Assembly
MEVV	Multi-Element Verification and Validation
MIR	Mission Integration Review
ML	Mobile Launcher
MPCV	Multi-Purpose Crew Vehicle
MPPF	Multi-Payload Processing Facility
MPS	Main Propulsion System
MSA	MPCV Stage Adapter
MSFC	Marshall Space Flight Center
N2	Nitrogen
NCA	Nose Cone Assembly

Acronym	Definition
NDE	Nondestructive Evaluation
NDS	Nitrogen Delivery System
O&C	Operations and Checkout
O/D	On Dock
OGV	Ogive Panel
OMS-E	Orbital Maneuvering System Engine
OSA	Orion Stage Adapter
OSMU	Orion Service Module Umbilical
OTP	Orion Transportation Pallet
OWG	Operations Working Group
P&O	Production and Operations
PCA	Pressurant Control Assembly
PCDU	Power Control Distribution Unit
PDU	Power Distribution Unit
PPE	Power and Propulsion Element
PQM	Propellant Qualification Model
PRT	Problem Resolution Team
PV	Pressure Vessel
QM	Qualification Motor
RCS	Reaction Control System
RWY	Raceway
SCCS	Spaceport Command and Control System
SIL	System Integration Lab
SITF	Software Integration Testing Facility
SRB	Solid Rocket Booster
SLS	Space Launch System
SSC	Stennis Space Center
STA	Structural Test Article
SW	Software
TLI	Translunar Injection
TLM	Telemetry
TPS	Thermal Protection System
TSM	Tail Service Mast
TSMU	Tail Service Mast Umbilical
TVC	Thrust Vector Control
UAS	Use As Is
ULA	United Launch Alliance
V&V	Verification and Validation
VAB	Vehicle Assembly Building
VAC	Vertical Assembly Center
VS	Vertical Stabilizer
WDR	Wet Dress Rehearsal
WSTF	White Sands Test Facility




# Orion









# EM2



*EM-2 Service Module  
Primary Structure*



*EM-2 Barrel*



*EM-2 Cone Section*



*EM-2 Pressure Vessel*



# EM-1 AND AA-2 LAUNCH ABORT SYSTEM (LAS)


(LOCKHEED)



NAC - March 26, 2018

27

- ✓ LAS EM-1 Fillets & Ogive panels delivered to MAF - November 2017
- EM-1 LAS Fairing assy components ship in place - February thru July 2018
- AA-2 LAS Jettison Motor (JM) On Dock (O/D) KSC - April 2018
- EM-1 LAS JM delivery available - July 2018 (ship in place)
- AA-2 LAS Fairing assy components O/D KSC - August thru December 2018
- AA-2 LAS Attitude Control Motor O/D KSC - August 2018
- AA-2 LAS Abort Motor O/D KSC - August 2018
- AA-2 Launch - April 2019



*Graphical Representation of LAS During AA-2 Test (scheduled April 2019)*



Ogive & Fillet Panels  
Fabrication  
complete



EM-1 Jettison  
Motor Available



EM-1 Fairing  
components  
available



AA-2 Fairing  
components O/D  
KSC



AA-2 Motors  
O/D KSC



AA-2  
Launch

# EM-1 CREW MODULE (CM)

## (KSC O&C BUILDING)




NAC - March 26, 2018

28

- ✓ CM module level test completed - November 2017
  - ✓ 28 test procedures, functionally tested all systems
- ✓ CM thermal cycle testing completed - December 2017
  - ✓ 2 full cycles, 28F to 127F
- ✓ Heatshield and Backshell fit ups completed - January 2018
- ✓ Heatshield painting and fitcheck completed - February 2018
- Propylene Glycol Water (PGW) accumulator R&R in work
- Heatshield Installation - March 2018 (waiting for PGW R&R)
- Side Hatch installation & leak tests - May 2018
- Reinstall reworked avionics (hybrid issue) - May 2018
- CM Direct Field Acoustics Test (DFAT) - July 2018
- CM Complete - August 2018



*EM-1 CM Backshell*



*EM-1 Heat Shield Skin*



*EM-1 Heat Shield Painted*



CM module level test



CM thermal cycle testing



HS and Backshell fit ups



Heatshield installation



Leak Testing



CM DFAT



CM/SM Mate

# EM-1 CREW MODULE ADAPTER (CMA)


(KSC O&C BUILDING)



NAC - March 26, 2018

29

- ✓ CMA subsystem integration completed - September 2017
- ✓ CMA end-to-end testing completed - December 2017
- Temp installation of Star Trackers - April 2018
- Install T-0 flight plate - April 2018
- Reinstall reworked avionics (hybrid issue) - May 2018
- Complete functional retests - June 2018
- Ready to mate with ESM - June 2018



*EM1 CMA in Clean Room*



CMA subsystem integration



CMA assembly  
operations and  
end-to-end testing



Install T-0



Install reworked  
avionics



Complete  
functional tests



# EM-1 SERVICE MODULE


(BREMEN, GERMANY)




NAC - March 26, 2018

30

- ✓ Installed ESM Thermal Control Unit (TCU) - June 2017 (R&R Board)
- ✓ Installed ESM Reaction Control System (RCS) Thruster - October 2017
- ✓ Pressurant Control Assembly (PCA) valves delivered to Bremen – March 2018
- RCS Flow Control Valve (FCU) Welds (U/R)
- ESM Power Control and Distribution Unit (PCDU) deliveries:
  - PCDU #1 – (EM-4 then PCDU #3)
  - PCDU #2 – (PCDU temp install, then PCDU#1)
- ESM N2 Tank installed - March 2018 (this week)
- ESM Prop Tanks installed - March 2018 (this week)
- ESM Orbital Maneuvering System Engine (OMS-E) installed - March 2018
- ESM Consumable Storage System (CSS) test complete - April 2018
- ESM PCA final integration complete - April 2018
- ESM Functional tests, March - June 2018
- ESM on dock at KSC - June 2018
- Step-1 Propellant Qualification Motor (PQM) testing complete - August 2018



*ESM-1 SM Integration*



*ESM-1 Flight Assembly – Lower level*



Thermal  
Control Unit  
Install



RCS Thruster  
Install



Prop Tanks  
Install



N2 Tank  
Install



OMS-E  
Install



Functional  
Tests



On Dock  
at KSC

# EM-1 CMA/ESM (KSC O&C BUILDING)



NAC - March 26, 2018

31

Integration Ops & Tests (KSC)


- CMA Ready to Mate - June 2018
- SM Delivery to KSC - June 2018
- CMA/ESM mate - July 2018
- CMA/ESM proof/leak test - August 2018
- SM thermal cycle test - August 2018
- SM Direct Field Acoustics Test (DFAT) - September 2018
- SM initial power up and functional tests - October 2018 – February 2019
- CM/SM Mate - December 2018

Testing (Plum Brook)

- CM/SM Transport to Plum Brook - February 2019
- CM/SM Environmental Testing (thermal vac, thermal balance, EMI/EMC) complete - June 2019
- CM/SM Transport to KSC - June 2019

Final Work (KSC)

- CM/SM Complete - July 2019
- CM/SM Turnover to EGS - July 2019



CMA/ESM  
Mate



CMA/ESM  
proof/leak  
test



SM initial power  
up/ functional  
tests



SM thermal  
cycle test



SM DFAT



CM/SM Mate



# FLIGHT SOFTWARE/INTEGRATED TEST LAB

(LM/DENVER)



NAC - March 26, 2018

32

## Software Development

- ✓ Flight Software load 28A released on 9/14/17 (Nominal Mission including On-Orbit, CM Fault Detection Isolation and Recovery (FDIR) except prop)
- ✓ Flight Software load 28B released on 12/19/17 (CM prop FDIR, EM-1 Onboard Network Config, Solar Array Control)
- ✓ Flight Software load 28C released 3/08/18 (Guidance, Navigation, and Control (GNC) commands, Ballistic Entry, Initial ESM FDIR, Video, Burn Plan Management)
- Flight Software load 28D on schedule for 5/31/18 (ESM FDIR, Ascent Aborts, Initial Backup Flight Software (BFS)/Safe Mode, Optical Navigation )
- Flight Software load 28E on schedule for 8/23/18 (Full GNC SM FDIR, BFS/Safe Mode, Redundancy Management)



**28A/B FSW  
Released**



**28C FSW  
Release**



**28D FSW  
Release**



**28E FSW  
Release**



**28F FSW  
Release**



**28G FSW  
Release**

## Integrated Test Lab (ITL)

- ✓ Completed 18 Nominal, Off Nominal and FDIR mission tests thru 2017
- ✓ ITL-03 CM Subsystem Integration & Assembly, Test, and Launch Operations (ATLO) Check out (C/O) ITL gap testing complete - February 2018
- ATLO IPO & CSM 28D functional testing complete - August 2018
- ATLO mission & CSM 28E testing complete - November 2018
- CSM 28F testing complete - February 2019
- ITL Test Campaign verification testing complete - May 2019



**Gap testing**



**28D functional  
testing**



**28E mission  
testing**



**CSM testing  
complete**



**ITL Test  
Campaign  
Verif complete**


# CAPSULE PARACHUTE ASSEMBLY SYSTEM (CPAS)

## CQT4-6 TEST CONOPS




NAC - March 26, 2018

33





# SLS








# EM2



*EM-2  
forward  
and center-  
forward  
booster  
segments*



*EM-2 Core Stage Engine Section*



*EUS RL-10 Engine P7001  
Injector LO2 Plate*



*EUS RL-10 Engine  
P7001  
Chamber  
Structural Jacket*

# EM-1 ICPS/MSA/LVSA

(MSFC/ULA-DECATUR)



NAC - March 26, 2018

36

- ✓ EM-1 Interim Cryogenic Propulsion Stage (ICPS) ship to United Launch Alliance at Cape Canaveral Air Force Station for final outfitting
- ✓ EM-1 ICPS Delivery to KSC - July 2017 (store in Space Station Processing Facility)
- ✓ EM-1 ICPS Hardware Acceptance Review - Oct 2017
- ✓ EM-1 OSA Production Complete - January 2018
- Orion Stage Adapter (OSA) Delivery to KSC - March 2018 (U/R)
- Launch Vehicle Stage Adapter (LVSA) Thermal Protection System (TPS) application complete - March 2018
- EM-1 LVSA Production Complete - August 2018
- LVSA Delivery to KSC - September 2018



*ICPS in SSPF*



*LVSA preps for Insulation*



*OSA in bracket installation*



ICPS  
Start  
Production



LVSA  
Start  
Production



ICPS  
Flight Unit  
Complete



OSA  
Flight Unit  
Complete



LVSA  
Flight Unit  
Complete



Delivery  
KSC




# EM-1 STAGES

(BOEING - MAF)



NAC - March 26, 2018

37



# CORE STAGE GREEN RUN




NAC - March 26, 2018

38




Pegasus Barge Transports CS1  
To SSC From MAF



Prep on the Tarmac  
For Loading into B-2 Stand



2 Crane Lift Into B-2 Stand




- Test 1: Modal Test (Suspended)
- Test 2: Vehicle Power-On Checks
- Test 3: MPS/Engine Leak Checks
- Test 4: Hydraulics and TVC Checks
- Test 5: Safing Checks for Wet Dress Rehearsal
- Test 6: Simulated Countdown and Hot Fire Test
- Test 7: Wet Dress Rehearsal




Test 8: Hot Fire CS1


62 Boeing  
Con-Ops  
Procedures  
While at  
SSC



Test 9: Refurbish in Stand



Prep on the Tarmac  
For Loading into Pegasus



Ship  
to KSC

# EM-1 BOOSTERS

(ATK - UTAH)




NAC - March 26, 2018

39

- ✓ All Booster Separation Motors are cast and finalized
- ✓ EM-1 Left & Right Hand Booster Production progressing
- ✓ All EM-1 Segment Casting complete
- ✓ Both Aft skirts structural refurbishment complete
- ✓ Both EM-1 Nozzle assemblies and Aft Exit Cones complete
- ✓ Avionics Qualification Testing Complete - October 2017
- ✓ EM-1 Left Hand aft skirt TVC lower frame installation complete
- ✓ 4 of 10 EM-1 Segments Finalized and in Storage (see note below)
  - Propellant-liner-insulation (PLI) complete - April 2018
  - EM-1 PLI Waiver signed – September 2018
  - EM-1 Segments Ready to Ship - November 2018

*Note: Flight worthiness of first 6 segments to be determined by leveraging the learning obtained during flight rationale development for EM-1*



*Thrust Vector Control Installation Progress in EM-1 Left Hand Aft Skirt*



QM-1  
Test



QM-2  
Test



EM-1  
First Segment  
Cast



EM-1 All  
Segments  
Cast



EM-1  
Segments  
Delivered

# EM-1 ENGINES

(AR - SSC)



NAC - March 26, 2018

40

- ✓ Held RS-25 Production Re-start Integrated Baseline Review (IBR) - May 2016
- ✓ Engine 0528 RS-25 (LOX Pump Pressure) Complete - Feb 2017
- ✓ Engine Control Unit (ECU) Flight Model (FM) -1 to 3 ATP Complete - Apr 2017
- ✓ Engine 0528 ECU Green Run Testing Complete
- ✓ EM-1 RS-25 Engines Deliver in Place - Oct 2017
  - *The EM-1 Flight Engines are Engine 2045, Engine 2056, Engine 2058, and Engine 2060*
- ✓ ECU Qualification Complete - Nov 2017
- ✓ Completion of three RS-25 Production Restart Development Hot Fire Testing Begins - Dec 2017 through Feb 2017
  - ✓ Includes successful testing of first major additive manufactured component: Pogo device
- 1<sup>st</sup> EM-2 (EM-1 spare) Engine (2063) Complete - August 2018



*Final Engine Adaptation / Software Cert Hot-fire Test*



*All 4 EM-1 Engines Delivered-in-place*



ECU  
Dev  
Testing



ECU FM1  
ATP  
Complete



ECU Green  
Run Testing  
Begins



EM-1  
Green Run  
Testing  
Complete



EM-1 RS-25  
Engines  
Delivered to  
MAF



# Software Test Lab

(MSFC)



NAC - March 26, 2018

41

## Software

- ✓ Deliver Flight Software Release 13 - December 2016
- ✓ Complete Sprint 5 Flight Software Release 14 - March 2017
- ✓ Complete Sprint 6 (final sprint) Flight Software Release 14 - May 2017
- Complete Release 14 Green Run Application Software (GRAS) - April 2018
- Complete Release 14 Flight Control Application Software (FCAS) - November 2018



**FSW 11**  
Release  
(Engineering)



**FSW 12**  
Release  
(Engineering)



**FSW 13**  
Release




**FSW 14**  
Release  
(GRAS)



**FSW 14**  
Release  
(FCAS)

## Software Integration Test Facility (SITF) - Qualification Testing

- ✓ Complete Phase 1 (Pwr Quality & Verif) - May 2016
- ✓ Complete Phase 2 (Command and Data Handling (C&DH) & Flight Safety System (FSS) Dry Run) - October 2016
- ✓ Complete Phase 3 (Flt Ctrl & Telemetry (TLM) Dry Run) - June 2017
- Complete Phase 4 (Final Avionics Verif) - June 2018



*SITF Qualification Testing*



**SITF**  
Development



**SITF**  
Qual Test  
Ph 1 Comp



**SITF**  
Qual Test –  
Ph 2 Comp



**SITF**  
Qual Test –  
Ph 3 Comp



**SITF**  
Qual Test  
Complete





# UMBILICAL LETF TESTING/MOBILE LAUNCHER

(LETF - KSC)




NAC - March 26, 2018

43

- ✓ Crew Access Arm (CAA) Installed – February 2018
- ✓ Interim Cryogenic Propulsion Stage Umbilical (ICPSU) Testing is complete; Ready to deliver to ML - February 2018
- ✓ LO2 TSMU Testing is complete; Ready to deliver to ML - February 2018
- LH2 TSMU Testing is underway; Ready to deliver to ML - April 2018
- ML Fit check at Pad – June 2018
- ML Roll to VAB
- ML/Pad Multi-element V&V

## EM-2 Development

- Design requirements for modification to ML for SLS Block 1B have been released to the Architect Engineer (A&E) (RS&H)



Crew Access Arm (CAA) Installed



Interim Cryo Propulsion Stage Umbilical (ICPSU)



LO2 Tail Service Mast Umbilical (TSMU)



LH2 TSMU



ML Fit Check at Pad



ML Roll to VAB




ML/Pad multi element V&V

## EM-1 Progress

- ✓ All vehicle access platforms have been installed and outfitting is complete
- ✓ VAB High Bay (HB) 3 elevators are complete
- ✓ GSE Handling and Access (H&A) fabrication and installation is complete
- ✓ Fire Alarm/Firex System Acceptance Testing is complete  
*(During Firex wet flow testing, the measured flow rates did not meet required values in two out of four zones; Follow on work to replace legacy valves and sprinklers to meet new pump pressure and continue mock-up testing with new nozzles)*
- Work on the Environmental Control System (ECS) continues; expected completion in March 2018

## EM-2 Development

- VAB ECS and HB 3/4 design continues
  - ✓ ECS 30% design review held January 17<sup>th</sup>
  - ✓ HB 3/4 30% design review held January 18<sup>th</sup>



All Platforms  
Installed



Platform Outfitting  
Complete



Handling and  
Access install



Fire Protection  
Systems



ME V&V





## EM-1 Progress

- ✓ Overall Pad B development is progressing well
- ✓ Ignition Over Pressure and Sound Suppression (IOPSS) Wet Flow Testing complete December 2017
- ✓ LH2 Liquid Gas Separator 100% complete
  - Flame Trench/ Deflector is 84% complete
  - Environmental Control System (ECS) refurbishment is 97% complete
- LO2 & LH2 Cryo Spheres fills are in progress to complete by April 2018



*IOPSS Wet Flow Test*

## EM-2 Development

- LH2 Storage Tank Design is over 60% complete
  - A&E Final Submittal expected in February 2018; Construction procurement activities will follow



*Flame Deflector*



Overpressure/  
Sound  
Suppression



Chillers



Deflector



Flame  
Trench



ECS



LH2 Storage Tank  
Fill

# MULTI-PAYLOAD PROCESSING FACILITY (MPPF)

(KSC)



NAC - March 26, 2018


46

MPPF standalone V&V activities are underway

- ✓ Crew Module Ammonia Servicing Subsystem (CMASS), Gaseous Nitrogen (GN2), Gaseous Oxygen (GO2), Gaseous Helium (GHe), and Kennedy Complex Control System (KCCS) V&V activities are complete
- ✓ Orion Transportation Pallet (OTP) was received and V&V is complete
- ✓ Ground Cooling System V&V Test Readiness Review completed - February 2018
- Hypergol Servicing/Deservicing testing is dependent on SCCS 4.0.1 validation
  - Cold Flow start targeted for March 2018
  - Hot Flow start targeted for May 2018
  - V&V complete expected in June 2018
- Done MPPF until Vehicle Processing



*CSM Simulator in Servicing Stand*



*Weight Simulation to be placed on OTP in 2018*



*SCAPE Ops Training*



V&V Start



CMASS Haz Testing



Orion Pallet Handling Complete



Hypers Testing Complete



MPPF V&V Complete



# Spaceport Command & Control System (SCCS)




NAC - March 26, 2018

47

- SCCS 4.0.1 - Hazardous Testing & GFAS Development/Test
- SCCS 5.0 – Orion flight vehicle processing & GFAS V&V
- SCCS 6.0 – GFAS Regression, ITCO, WDR and EM-1



MPPF Hazardous Testing



MEVV @ VAB



MEVV @ Pad

- SCCS 4.0 complete and transitioning to 4.0.1 in Firing Rooms (Feb 2018)
- SCCS 4.0.1 – System Test on schedule for planned start (Feb 2018)
- Validation complete (Mar 2018)

☒ SCCS 4.0  
Validated  
Release

☐ SCCS 4.0.1  
System Test

☐ SCCS 4.0.1  
Validated

☐ SCCS 5.0  
Engineering  
Release

☐ SCCS 5.0  
Validated

☐ SCCS 6.0  
Engineering  
Release

☐ SCCS 6.0  
Validated

## Ground Flight Application Software (GFAS)



- Completed initial GFAST testing at ITL & SIL with favorable results
- Continued prioritization of partnered cross program initiatives, challenges and deliverables

☒ GFAS Drop  
10 & 11

☒ GFAS  
(ECLSS/Hypers)  
V&V Complete

☐ GFAS Ready for  
ML/Pad ME V&V

☐ GFAS  
SC Offline  
Ready (SAR)

☐ GFAS ITCO  
Ready (SAR)