



Commercial Crew Program (CCP) NAC HEOMD Committee Status

Lisa Colloredo
Deputy Manager, Commercial Crew Program

November 29, 2017



Purpose & Agenda



- **Purpose:** To brief the NASA Advisory Council HEOMD Subcommittee on the latest status and technical progress for the CCP CCtCap and CCIcap contracts
- **Agenda:**
 - **CCP Execution Status**
 - Program Progress
 - Milestone Summary
 - Top Risks
 - **CCtCap Status**
 - Boeing Commercial Provider Status
 - SpaceX Commercial Provider Status
 - **CCiCap Status**
 - Blue Origin Status
 - Sierra Nevada Status
 - **Summary**



Program Progress



CCP has made significant progress over the last quarter, notably:

- **Program's Annual Review is complete**
 - Significant technical issues resolution and risk mitigations continue as CCP progresses toward flight tests and crewed missions to the International Space Station
 - Awarded Post Certification Missions (PCMs) 3-6 to both Providers
 - Multiple spacecraft and qualification test articles are in production and testing simultaneously
- **Mission planning and preparations for eight CCP missions are in work:**
 - Official Dates For Boeing:
 - August 2018: Orbital Flight Test (unmanned demo)
 - November 2018: Crewed Flight Test (demo)
 - PCM-1 awarded May 2015; Completed four milestones to date
 - PCM-2 awarded in December 2015; Completed four milestones to date
 - Official Dates For SpaceX:
 - April 2018: Flight to ISS without crew (Demo Mission 1)
 - August 2018: Flight to ISS with crew (Demo Mission 2)
 - PCM-1 awarded November 2015; Completed three milestones to date
 - PCM-2 awarded July 2016; Completed two milestones to date



Program Progress Continued



- Both providers are making tangible progress toward flight tests and crewed missions to the International Space Station
- Space hardware manufacturing, testing and qualification are underway
- Continued engagement as the providers perform critical test and verification events
- Continue to make progress in the burn down of key certification products with the providers
 - Progress for each provider is included in provider-specific sections of this briefing




Commercial Crew & Cargo Processing Facility




Horizontal Integration Facility



Milestones Boeing



Milestones SpaceX



Required Milestone



Boeing Milestone



SpaceX Milestone

CCtCapCMS - Sep 1,2017
Data Source: Boeing FY17Q3 / SpaceX FY17Q3
POC: Debbie Cole, 321-867-0834



CCP Top Programmatic Risks


11/7/2017



Programmatic Risk = Likelihood x (Highest of Non Safety Consequences (C, S, P))

LxC	Trend	Risk Title	Risk ID Number	Office
3x5	NC	Inability to Meet LOC	CCP-SEI-2015-1	SE&I
5x2	New	Cost of Government Provided Services (ISS CR-15654)	CCP-GMO-2017-1	GMO
2x4	NC	DoD Search and Rescue Training Schedule	CCP-GMO-2015-4	GMO

Trend Key: NC = No Change, I = Increase in Risk, D = Decrease in Risk





CCP Top Program Safety Risks

11/7/2017



Safety Risk = Safety Likelihood x (Highest of Safety Consequences (Sp, Sf, Se))

LxC	Trend	Risk Title	Risk ID Number	Office
4x5	NC	Inability to meet LOC	CCP-SEI-2015-1	SE&I
3x5	NC	Aborting into Sea States with Unsafe Rescue	CCP-GMO-2016-3	GMO
3x3	NC	Crew Entry Accelerations and Spaceflight Associated Neuro-ocular Syndrome (SANS) Exacerbations	CCP-IP-2016-3	IP

Trend Key: NC = No Change, I = Increase in Risk, D = Decrease in Risk

5					
4					1
3			1		1
2					
1					
	1	2		4	5

Likelihood

Consequence



Boeing Commercial Provider Status





Boeing Accomplishments



- **Design, Demonstration, Test, and Evaluation**

- Nine Land Landing Qualification Tests completed as of 9/28 (14 planned)
- Parachute System Qualification Test #2 completed in October
- Completed a joint orbital flight test, rendezvous and docking paper simulation with the ISS
- Structural Test Article (STA) initial Shock Testing complete
 - Modal Testing completed in September
 - Launch Vehicle Adapter aeroskirt shipped to Huntington Beach to support future Jettison and Separation tests
- Completed a crew emergency egress system demonstration
- WSTF hot fire testing
 - First LAE acceptance hot fire test completed with pathfinder engine
 - LAE test sequence of shipsets (CFT, PCM's) and SMHF qual testing in work
 - Service Module Hot Fire test article shipped to WSTF
 - Cold flow testing in work
- ISS DCR planning and execution continues
 - ULA Phase III progressing with first STRB completed in October
 - Partnered Spacecraft Phase III ground-rules with ISS and Boeing



Land Landing Qualification Test



LC-41 Emergency Egress



STA in Modal Test Config




Boeing Accomplishments



• Production & Operations


- Flight unit assembly on several key spacecraft structures and mechanisms
 - Service Module Hot Fire (SMHF) Test Article systems acceptance test complete
 - Spacecraft 1 (SC1) crew module upper and lower domes mated
 - Landing airbags integrated onto SC1 lower dome
 - Landing and Recovery System (LRS) pressure tank installation and leak tests complete
 - Pressure Control System (PCS) proof pressure test complete
 - Pad Abort Service Module 1 (SM1) Strong backs, bridge beams, isogrid panels, and radiator panels installed
 - Spacecraft 2 (SC2) upper dome bucket handle installed and IVA hatch installation in work to support proof pressure test
 - Spacecraft 3 (SC3) A-Frames installed on lower dome
 - ISS delivered 2 NDS flight units to Boeing
- Atlas AV-080 OFT Launch Vehicle
 - Dual Engine Centaur (DEC) tank in high pressure test cell
 - Booster RP-1 tank weld completed, in hydrostatic test
 - Booster LOX tank upper barrel in friction stir weld; lower barrel weld and x-ray complete
- Operations training preparations
 - Boilerplate-3 delivered to NASA for future water rescue training
 - Crew training plan delivered, NASA review in work



Service Module Hot Fire Test Article



Spacecraft 1 Assembly



Spacecraft 1 Crew Module



SpaceX Commercial Provider Status





SpaceX Accomplishments



- **Design, Demonstration, Test, & Evaluation**

- Dragon

- Demo-1 capsule integration mate complete
 - Qualification module structural testing complete
 - Demo-1 schedule efficiencies implemented
 - Continuing maturation of displays & controls, crew interfaces and operations; began joint sims and training
 - Completed initial Dragon to C2V2 RF Interface Test (Joint Test 9a) with ISS
 - 8 parachute drop tests held to date
 - Validation propulsion module buildup and test facility upgrades in work
 - 2 Hardware-in-the-Loop (HITL) tables assembled in support of software testing

- Falcon9


- Merlin 1D and MVAC in qualification testing
 - Performing Block 5 CDR reviews
 - Continuing COPV 2.0 development and beginning qualification

- Ground Systems (LC-39A)

- Lightning tower upgrades complete
 - Crew access arm and white room installation planned for upcoming months

- Certification Products

- (30) VCNs have been approved:
 - (25) for SSP 50808 and (5) for CCP 1130





SpaceX Accomplishments



- **Production & Operations**

- Flight unit assembly on several key spacecraft structures and mechanisms
 - 3 Dragon Crew Modules in production:
 - Demo-1 service section integration complete and Demo-1 Avionics rack assembled
 - Demo-2 mechanical integration nearing completion
 - Crew-1 (PCM 1) weldment seeing significant progress
 - Demo-1, Demo-2 and IFAT trunks in production
- Operations Training
 - Uncrewed
 - Completed first Demo-1 simulation
 - Launch operations continuing from LC-39A
 - Crewed
 - Supported Dragon Rescue Trainer DET-3 training
 - Buck mechanical assembly complete including all cabin panels, storage bins and seats



Dragon 2 Capsule



Rescue Trainer



Demo 2 Trunk



Crew 1 Weldment



Cabin Mock Up



Blue Origin Accomplishments



Commercial Space Capabilities Collaboration (CSCC)

Space Act Agreement (SAA)

- **Technical Exchanges**

- Launch Vehicle Structures and Materials
- Reentry Aeroheating
- Effects of Lightning on Launch Vehicle
- Doppler Radar
- Structural Loads
- Milestone #4: November 2017
 - Progress Review of Rocket Propulsion Systems (Blue Origin Facility)

- **Data Exchange**

- Various software requests and technical documentation exchanges in work

- **Look Ahead**

- Milestone #5, May 2018
 - Development Update of Launch Site
- Continued Technical and Data Exchange



BE-3 in Test Stand




BE-4 Test Fire



Sierra Nevada Corp. Accomplishments



- **Successfully performed Full scale Dream Chaser engineering test article (ETA) unpowered approach & landing test (ALT-2) at Armstrong Flight Research Center - Edwards Air Force Base on 11 Nov. 2017**
 - ALT-2 Free-flight including detailed flight maneuvers was nominal
 - ETA landing and rollout were successful
 - SNC Post-flight data analysis is currently underway
 - CCIcap SAA Milestone 4b NASA outbrief scheduled for Dec. 2017
 - Several integrated tests performed to verify system design requirements and validate system functions in preparation for ALT-2 test
 - Day In The Life Test (final) – Aug. 2017
 - Combined Systems Test (final) – Aug. 2017
 - Captive Carry Test #1 & #2 – Aug./Sept. 2017



Dream Chaser ETA




CCP Summary



- **CCP continues to facilitate the development and certification of U.S. industry-based crew transportation systems**
- **Boeing and SpaceX are meeting contractual milestones and maturing their designs**
 - A significant amount of hardware is in development, test and qualification in preparation for upcoming missions
 - Risks are being identified and important design challenges are being addressed
 - NASA is engaged in meaningful insight
- **Both providers are making tangible progress toward flight tests and crewed missions to the International Space Station**
- **CCP has robust and efficient processes for certification including addressing waivers and deviations**
 - Progress is being made in the burn down of key certification products with the providers
- **In preparation for flight, there is significant work ahead**









Acronyms & Abbreviations



- **ALT:** Approach & Landing Test
- **AoA:** Angle of Attack
- **ATCS:** Active Thermal Control Subsystem
- **BP:** Boilerplate
- **Calysto:** Risk Management tool
- **C3PF:** Commercial Crew and Cargo Processing Facility
- **CCiCap:** Commercial Crew integrated Capability
- **CCtCap:** Commercial Crew transportation Capability
- **CDR:** Critical Design Review
- **CFA:** Computational Fluid Analysis
- **CFT:** Crewed Flight Test
- **CM:** Crew Module
- **COPV:** Composite Overwrap Pressure Vessel
- **CPWSR:** Configuration Performance & Weight Status Report
- **CSCS:** Contingency Spacecraft Crew Support?
- **CTS:** Crew Transportation System
- **DCR:** Design Certification Review
- **DDT&E:** Design, Development, Test & Evaluation
- **Det3:** (USAF) Detachment 3
- **DM:** Demonstration Mission
- **ECLSS:** Environmental Control and Life Support System
- **ECM:** Electro-Chemical Machining
- **EDM:** Electron Discharge Machining
- **EDS:** Emergency Detection System
- **ETA:** Engineering Test Article
- **FHS:** Forward Heat Shield
- **FLT:** Flight
- **FOD:** Flight Operations Directorate
- **FTCR:** Flight Test Certification Review
- **GMO:** Ground & Mission Operations
- **HAR:** Hazard Analysis Report
- **HITL:** Human in the Loop
- **HR:** Hazard Report
- **HRCP:** Human Rating Certification Package
- **IDA:** International Docking Adapter
- **IFA:** In-Flight Abort
- **IV&V:** Independent Verification & Validation
- **JIRA:** Project management software tool
- **JPRCB:** Joint Program Requirements Control Board
- **JT:** Joint Test
- **LAE:** Launch Abort Engine
- **LLQTL:** Land Landing Qualification Test
- **LOC:** Loss of Crew
- **LOM:** Loss of Mission
- **LSC:** Linear Shaped Charge
- **LSORR:** Launch Site Operational Readiness Review
- **LV:** Launch Vehicle
- **LVA:** Launch Vehicle Adapter
- **MIR:** Mission Integration Review
- **MMOD:** Micrometeoroid and Orbital Debris
- **MVac:** Merlin Vacuum Engine
- **NDS:** NASA Docking System
- **NBL:** Neutral Buoyancy Lab
- **NESC:** NASA Engineering & Safety Center
- **NLA:** Non-Linear Aero
- **OFT:** Orbital Flight Test
- **OMAC:** Orbital Maneuvering and Attitude Control
- **OML:** Outer Mold Line
- **ORDEM:** Orbital Debris Engineering Model
- **ORR:** Operational Readiness Review
- **PAA:** Product Assurance Analysis
- **PAFB:** Patrick Air Force Base
- **PAT:** Pad Abort Test
- **PC&I:** Program Control & Integration
- **PCB:** Program Control Board
- **PCDTV:** Parachute Compartment Drop Test Vehicle
- **PCM:** Post Certification Mission
- **PDR:** Preliminary Design Review
- **PnP:** Probability of No Penetration
- **PSA:** Probabilistic Safety Analysis
- **PJ:** Para Jumpers
- **RCS:** Reaction Control System
- **RT:** Rescue Trainer
- **SC:** Spacecraft
- **SE&I:** Systems Engineering & Integration
- **SM:** Service Module
- **SOW:** Statement of Work
- **STA:** Structural Test Article
- **STRB:** Safety Technical Review Board
- **SureSep:** LVA Jettison System
- **TIM:** Technical Interchange Meeting
- **TM3:** Targeted Mass 3
- **TPS:** Thermal Protection System
- **TTP:** Tactics, Techniques, & Procedures
- **TRR:** Test Readiness Review
- **UDA:** Universal Docking Adapter
- **ULA:** United Launch Alliance
- **USAF:** US Air Force
- **VBR:** Vehicle Baseline Review
- **VCN:** Verification Closure Notice
- **VE:** Verification Event
- **VIIP:** Vision Impairment/Intracranial Pressure
- **WSTF:** White Sands Test Facility
- **WTT:** Wind Tunnel Testing