

A composite image showing the Orion spacecraft and the Space Launch System (SLS) rocket in space. The Orion spacecraft is on the right, with its solar panels deployed. The SLS rocket is on the left, with its orange external tank and white boosters. The background is the Earth's surface and the blackness of space.

Exploration Systems Development Update

Tom Whitmeyer, Acting Deputy Associate Administrator for
Exploration Systems Development

NASA Advisory Council (NAC)
October 30, 2019

Artemis I Status



Exploration Systems Development Update October 30, 2019

2

- ✓ European Service Module Critical Design Review
- ✓ Crew Module Pressure Proof Test
- ✓ Booster Qualification Motor 2 Test
- ✓ Crew Module Propellant Pressure Proof Test
- ✓ VAB Verification & Validation Complete
- ✓ RS-25 Flight Engines Complete
- ✓ ICPS Delivered to KSC
- ✓ Crew Module Initial Power On
- ✓ VAB High Bay Construction Complete
- ✓ Multi-Payload Processing Facility Construction
- ✓ LVSA Manufacturing Complete
- ✓ Mobile Launcher (ML) Umbilicals Installed
- ✓ VAC Welding Complete on Core Stage
- ✓ Launch Pad Flame Trench Construction Complete
- ✓ Parachute Tests Complete
- ✓ European Service Module Delivered to KSC
- ✓ Crew Module and Service Module Mate
 - All Orion Splash-down Recovery Tests Complete*
 - Core Stage Integration
 - ML Ground Support Equipment Installation Complete

- Core Stage Green Run Hot Fire Test
- Crew and Service Module Delivery to EGS
- Ground Flight Application Software Complete
- Booster Stacking in VAB
- Core Stage Arrival at KSC
- Core Stage Stacking with Boosters in VAB
- CM/SM Mating with Launch Abort System
- Orion Mating with SLS in VAB
- Wet Dress Rehearsal at Launch Pad
- Roll-out for Launch


*Known as Underway Recovery Tests – NASA and the U.S. Navy are conducting Underway Recovery Tests to verify and validate procedures and hardware that will be used to recover the Orion spacecraft after it splashes down in the Pacific Ocean following deep space exploration missions.



Building to Artemis I



Exploration Systems Development Update October 30, 2019



✓ 4 Artemis I Engines



National Aeronautics and
Space Administration

A background image of a space shuttle launch. A bright orange and white plume of fire and smoke trails from the bottom left towards the top center, curving upwards. The bottom of the image shows a view of Earth from space, with a blue horizon and white clouds. The word "EXPLORE" is centered in the middle of the image in a large, white, sans-serif font. The letter "O" is replaced by a detailed image of the Moon, showing its craters and maria.

EXPLORE

Orion Spacecraft




Exploration Systems Development Update October 30, 2019

5



Completed Orion Crew Vehicle for Artemis I flight in the Operations & Checkout Building at NASA's Kennedy Space Center in Florida.



Aug. 5 Propulsion Qualification Test - a successful, continuous 12-minute firing of Orion's propulsion system.



Launch of NASA's Ascent Abort-2 successfully demonstrated the Launch Abort System on July 2, 2019.

Artemis I Launch Abort System (LAS) (Lockheed)

Exploration Systems Development Update October 30, 2019

6

- ✓ LAS assembly and integration complete
- System Acceptance Review (SAR) and Design Certification Review (DCR) – mid-November 2019
- LAS DD250 - November 2019



Orion Launch Abort System



AA-2 Motors O/D
KSC



Artemis I Jettison
Motor Available



AA-2
Motors
O/D KSC



AA-2 Launch



LAS Tower
Integration



LAS
Complete

Ascent Abort (AA)-2 Test Findings/Results

Exploration Systems Development Update October 30, 2019

7



- 38 Total AA-2 Flight Test Objectives (FTOs) were assessed at an Engineering Review Board (ERB) on August 21, 2019
- Preliminary assessments of FTOs are positive
- AA-2 flight test results scheduled to be finalized on November 20, 2019

Expect AA-2 Flight Test will be deemed fully successful

Artemis I Crew and Service Module (CSM) (KSC O&C Building)

Exploration Systems Development Update October 30, 2019

8

- ✓ CM/SM Mate to form CSM - July 2019
- ✓ CSM Final Assembly and System Testing (FAST) Cell Operations - July – October 2019
 - ✓ CSM Initial Power Up
 - ✓ CSM Subsystem Integration
 - ✓ CSM Integration Spacecraft Testing
 - ✓ Complete CSM Assembly
- CSM Transport to Plum Brook – November 2019



*Drogue Mortar being installed
Side Hatch TPS Panel Installed*



CM/SM Mate



CSM FAST Cell Operations




Transport to Plum Brook

Artemis I CSM Environmental Testing (Plum Brook Station (PBS))

Exploration Systems Development Update October 30, 2019

9

- CSM Received at PBS– November 2019
- CSM Thermal Balance Test complete – January 2020
- CSM Thermal Vacuum Test complete – February 2020
- CSM Electromagnetic Interference and Electromagnetic Compatibility (EMI/EMC) Test complete – March 2020
- CSM Transport to KSC – March 2020



Concept imagery of Orion Crew and Service Module testing at Plum Brook Station

☐ CSM Received at PBS

☐ CSM Thermal Balance
Test

☐ CSM Thermal Vacuum
Test

☐ CSM
EMI/EMC Test


☐ CSM to KSC

Artemis I CSM Final Assembly and Test (KSC O&C Building)

Exploration Systems Development Update October 30, 2019

10

- CSM Return to KSC – March 2020
- CSM Final Assembly and Test – March 2020 – May 2020
- CSM Complete – May 2020
- CSM Turnover to EGS – May 2020



Flight Software/Integrated Test Lab (Lockheed Martin/Denver)

Exploration Systems Development Update October 30, 2019

11

Software Development

Artemis I

- ✓ Flight Software load 28E released 9/24/18 (Guidance, Navigation and Control, Fault Detection Isolation and Recovery, Safe Mode, Backup Flight System, and Redundancy Management)
- ✓ Flight Software Load 28E-Patch 1 release 10/25/18
- ✓ Flight Software Load 28E-Patch 2 release 12/17/18
- ✓ Flight Software Load 28E – Patch 3 release - 2/28/19
- ✓ Flight Software Load 28E – Patch 4 release – 4/28/19
- ✓ Flight Software Load 28E – Patch 5 release - 6/30/19
- Flight Software Load 28E – Patch 6 release – 12/12/19
- Flight Software Load 28E – Patch 7 release – April 2020

Software Development

Artemis II

- Software Build 201 Formal Software Release – March 2020
- Software Build 202 Formal Software Release – July 2020
- Software Build 203 Formal Software Release – October 2020



28E Patch 1
Release



28E Patch 2
Release



28E Patch 3
Release



28E Patch
4 Release



28E Patch 5
Release



28E Patch 6
Release



28E Patch 6
Release



Artemis II
Release 201



Artemis II
Release 202

Integrated Test Lab (ITL)

- ✓ Assembly, Test, and Launch Operations mission & CSM 28E Functional testing complete – July 2019
- ✓ ITL Verification Test Campaign complete for Artemis I– September 2019
- Reconfigure ITL to support both Artemis I and Artemis II testing – November 2019



ATLO mission & CSM 28E
Functional testing complete



ITL Verif Test Campaign
complete – Artemis I



ITL Reconfig to support
Artemis I & II

Build up of Artemis II Crew Module (CM) (Kennedy Space Center Operations & Checkout (O&C) Building)

Exploration Systems Development Update October 30, 2019

12

- ✓ CM Pressure Vessels Arrives at O&C – August 2018
- ✓ CM Primary Structure – Bird Cage Complete – January 2019
- ✓ CM Proof Pressure Test – February 2019
- ✓ Heatshield/Lower Backshell Prefit – July 2019
- ECLSS Wall Drilling, Secondary Structure, ECLSS, Prop, & Component Installation – November 2019
- CM ECLSS/Prop Proof Pressure Leak Test –
 - Phase 1 - April 2020
 - Phase 2 – August 2020
- Artemis II Core Avionics Delivered – August 2020
- CM Subsystem Installations – January - August 2020
- CM Functional Tests – February 2021
- Heatshield Installation – January 2021
- CM Back Shell, Forward Bay Cover and Avionics Installation – April 2021
- CM ready to mate – April 2021



Artemis II Crew Module at the O&C

<input checked="" type="checkbox"/>	CM Bird Cage Complete	<input checked="" type="checkbox"/>	CM Proof Pressure Test	<input checked="" type="checkbox"/>	Heatshield/Lower Backshell Prefit	<input type="checkbox"/>	ECLSS Installation	<input type="checkbox"/>	ECLSS/Prop Proof Pressure Test	<input type="checkbox"/>	Subsystem Installation	<input type="checkbox"/>	Functional Tests	<input type="checkbox"/>	Heatshield installation	<input type="checkbox"/>	CM Back Shell, FW Bay Cover, Avionics Installation	<input type="checkbox"/>	CM ready to mate
-------------------------------------	-----------------------	-------------------------------------	------------------------	-------------------------------------	-----------------------------------	--------------------------	--------------------	--------------------------	--------------------------------	--------------------------	------------------------	--------------------------	------------------	--------------------------	-------------------------	--------------------------	--	--------------------------	------------------

Artemis II Crew Module Adapter (CMA) (KSC O&C Building)

Exploration Systems Development Update October 30, 2019

13

- ✓ CMA Structural Assembly – October 2019
- CMA Secondary Structure and Clean Room Ops – January 2020
- CMA Leak/Proof Tests – February 2020
- CMA Subsystem Installation – March 2020
- Complete Functional Test – May 2020
- Ready to Mate with the European Service Module - May 2020



CMA Structural
Assembly



Secondary Structure



Leak/Proof
Test



Subsystem
Installation



Complete
Functional Test




CMA Ready to
Mate

Space Launch System (SLS) Rocket

Exploration Systems Development Update October 30, 2019


14



VAB crane lowers the SLS Core Stage Pathfinder into High Bay 3



The first of four RS-25 engines has been attached to the core stage




Liquid oxygen tank structural test article placed into Test Stand 4697 at NASA's Marshall Space Flight Center.

Artemis I Stages (Boeing - MAF)

Exploration Systems Development Update October 30, 2019

15



☒ Weld Confidence Articles

☒ All CS 1 VAC Complete

☒ FS Complete

☒ IT Complete

☒ LOX Tank Complete

☒ Forward Join

☒ LH2 Tank Complete

☒ ES Complete

☒ Horiz. Join

☐ Final Integration


☐ Ship to Green Run

Artemis I Green Run

Exploration Systems Development Update October 30, 2019

16

- Core Stage Ship to SSC - December 2019
 - Core Stage Load into B-2 Test Stand
 - Modal Test Complete
 - Vehicle Power-on Checks Complete
 - Main Propulsion System (MPS) & Engine Leak / Functional Checks Complete
 - Hydraulics and Thrust Vector Control (TVC) Checks Complete
 - Safing Checks for Wet Dress Rehearsal Complete
 - Simulation Countdown Complete
 - Wet Dress Rehearsal Complete
 - Hot-Fire Test Complete
 - Post Hot-Fire Refurbishment
 - Post Green Run Final Health and Status Check -
- Core Stage Ship to KSC



Artemis I Boosters (Northrop Grumman - Utah)

Exploration Systems Development Update October 30, 2019

17

- ✓ All Booster Separation Motors are cast and finalized
- ✓ All Artemis I Segment Casting complete (10 out of 10 Artemis I segments cast)
- ✓ Both Aft skirts structural refurbishment complete
- ✓ Both Artemis I Nozzle assemblies and Aft Exit Cones complete
- ✓ Avionics Qualification Testing Complete
- ✓ Artemis I Left Hand aft skirt TVC lower frame installation complete
- ✓ All 10 Artemis I Segments Finalized and in Storage
- ✓ Propellant-liner-insulation (PLI) flight rationale complete - November 2018
- ✓ Artemis I PLI Waiver signed – May 2019
- Artemis I Segments Ready to Ship – Plan to ship by March 2020 (warmer weather to ship from Utah)
- Booster stacking



Final Artemis 1 segment to storage



Engineers remove the core after casting the booster case with propellant



Qualification
Motor (QM)-1
Test



QM-2
Test



Artemis I
First Segment
Cast



Artemis I All
Segments
Cast



Artemis I
Segments
Delivered



Artemis I
Segments
Stacked

Artemis I & II Engines (Aerojet Rocketdyne – MAF & SSC)

Exploration Systems Development Update October 30, 2019

18

- ✓ Held RS-25 Production Re-start Integrated Baseline Review (IBR) - May 2016
- ✓ Engine 0528 RS-25 (LOX Pump Pressure) Complete - February 2017
- ✓ Engine Control Unit (ECU) Flight Model (FM) -1 to 3 Authority To Proceed (ATP) Complete - April 2017
- ✓ Engine 0528 ECU Green Run Testing Complete
- ✓ Artemis I RS-25 Engines Deliver in Place - October 2017
 - The Artemis I Flight Engines are Engine 2045, Engine 2056, Engine 2058, and Engine 2060*
- ✓ RS-25 Development Test Campaign (First Hot Isostatic Pressure bonded Main Combustion Chamber and Controller Green Runs) - August 2018 through April 2019
 - Artemis II (Artemis I contingency engines) Engines Complete
 - ✓ E2059
 - ✓ E2047
 - E2063
 - E2062
 - Engine Installation into Core Stage 1 – CURRENTLY IN PROGRESS @ MAF



Final Engine Adaptation / Software Cert Hot-fire Test



Artemis I Engine #2 Installation



ECU
Dev
Testing



ECU FM1 ATP
Complete



ECU Green Run
Testing Begins



Artemis I Green Run
Testing Complete



Artemis I RS 25
Engines Delivered to
MAF



Engine Installations
into Core Stage

Software Test Lab (Marshall Space Flight Center)

Exploration Systems Development Update October 30, 2019

19

Software

- ✓ Deliver Flight Software Release 13 - December 2016
- ✓ Complete Sprint 5 Flight Software Release 14 - March 2017
- ✓ Complete Sprint 6 (final sprint) Flight Software Release 14 - May 2017
- ✓ Complete Release 14 Green Run Application Software (GRAS) - June 2018
- ✓ Complete GRAS Regression Testing – January 2019
- ✓ Complete Release 14 Flight Control Application Software (FCAS) - July 2019

✓ FSW 11
Release
(Engineering)

✓ FSW 12
Release
(Engineering)


✓ FSW 13
Release

✓ FSW 14
Release
(GRAS)

✓ FSW 14
Release
(FCAS)

Software Integration Test Facility (SITF) - Qualification Testing

- ✓ Complete Phase 1 (Pwr Quality & Verif) - May 2016
- ✓ Complete Phase 2 (Command and Data Handling (C&DH) & Flight Safety System (FSS) Dry Run) - October 2016
- ✓ Complete Phase 3 (Flt Ctrl & Telemetry (TLM) Dry Run) - June 2017
- ✓ Complete Avionics Subsystem Qualification Testing - May 2019
- Complete Phase 4 (Final Avionics Verif) - November 2019 – IN PROGRESS



SITF Qualification Testing

✓ SITF
Development

✓ SITF
Qual Test
Ph 1 Comp

✓ SITF
Qual Test –
Ph 2 Comp

✓ SITF
Qual Test –
Ph 3 Comp

✓ SITF
Qual Test –
Avionics Test Comp

□ SITF
Qual Test
Complete

Artemis II SLS Progress

Exploration Systems Development Update October 30, 2019

20

- ✓ All (10 out of 10) Artemis II Segment Casting complete
- ✓ All 10 Artemis II Segments Finalized and in Storage in Utah
- Artemis II (Artemis I contingency engines) Engines Complete
- Forward Skirt Complete
- Intertank Complete
- LOX Tank Complete
- Forward Join
- LH2 Tank Complete
- Engine Section Complete
- Horizontal Join
- Engines Installed




Artemis II LVSA
OSA Panels



Artemis II Boosters Segments Cast



Artemis II Engine Section



Artemis II LH2 Tank in VAC
@ MAF



Boosters



Engines
Complete



FS
Complete



IT
Complete



LOX Tank
Complete



Forward
Join



LH2 Tank
Complete



ES
Complete



Horiz.
Join



Engines
Installed



Ship to
KSC

Exploration Ground Systems

Exploration Systems Development Update October 30, 2019

21



Completed the Rotation Processing and Surge Facility (RPSF) System Acceptance Review / Operational Readiness Review. The RPSF will receive the booster segments for the SLS rocket.



A flow test of the Ignition Overpressure Protection and Sound Suppression water deluge system on the mobile launcher. The mobile launcher is undergoing final testing and checkouts at Launch Pad 39B



Core Stage Pathfinder moved into the VAB for training operations

Mobile Launcher (ML) (KSC)

Exploration Systems Development Update October 30, 2019

22

Artemis I Progress

- ✓ ML Roll to VAB – September 2018
- ✓ ML Roll to Pad – June 2019
- ✓ ML Pneumatics Functional Testing Completed – September 2019
- ✓ ML Simultaneous Retract Completed – October 2019
- ✓ ML End To End (ETE) Electrical V&V Completed – October 2019
- ML/Pad LO2/LH2 Systems Verification and Validation (V&V) Complete – November 2019
- ML/Pad Multi-Element (ME) V&V Complete – November 2019
- ML ETE Fluid V&V Complete – December 2019

Future Mission Development

- ✓ ML-2 Contract Award (Artemis IV) – June 2019
- ✓ ML-1 Crewed Modifications Design Award (Artemis II) – August 2019
- ✓ ML-2 Charrettes & Studies Completed (Artemis IV) – October 2019
- ML-2 Construction Start (Artemis IV) – November 2019



ML at Pad 39B for ME V&V



ML Roll to VAB



ML Roll to Pad



ML Pneumatics Functional Test



ML Simultaneous Retract



ML ETE Electrical V&V



ML/Pad LH2/LO2 V&V



ML/Pad ME V&V



ML ETE Fluid V&V

Vehicle Assembly Building (VAB) (KSC)

Exploration Systems Development Update October 30, 2019


23

Artemis I Progress

- ✓ Testing on the Environmental Control System (ECS) for Artemis I Completed – September 2018
- ✓ VAB Handling & Access Design Certification Review (DCR) Completed – May 2019
 - VAB Integrated Platform Demonstrations – November 2019
 - VAB Platforms DCR – November 2019
 - VAB Subsystem Transitions – November 2019

Future Mission Development

- ✓ VAB High Bay (HB) 3 Platform Design Completed (Artemis IV) – March 2019
- ✓ VAB ECS Construction Started (Artemis II) - April 2019
 - VAB HB3 Platforms Construction Start (Artemis IV) – TBD



VAB HB3 Platforms surrounding ML



Testing on
ECS for
Artemis I



VAB Handling &
Access DCR



VAB Integrated
Platform Demo



VAB
Platforms
DCR



VAB Subsystem
Transitions
Complete

Pad 39B (KSC)

Exploration Systems Development Update October 30, 2019

24

Artemis I Progress

- ✓ Flame Trench/Flame Deflector Completed – September 2018
- ✓ Pad B ECS Test Readiness Review (TRR) Completed – October 2018
- ✓ Pad B ECS Testing Completed – December 2018
- ✓ Pad B Extensible Columns Fabrication Completed – April 2019
- ✓ Pad B Ready for ML – June 2019
- ✓ Pad B Extensible Columns Testing Completed – October 2019
- ML/Pad Multi-Element V&V Complete – November 2019
- ML/Pad ECS V&V Testing Complete – November 2019

Future Mission Development

- ✓ Emergency Egress System (EES) Concept study extension to evaluate ML-1 and ML-2 interchangeability (Artemis II) - Completed
- ✓ LH2 Sphere Dewar Support Columns Installed (Artemis IV) – July 2019
- ✓ LH2 Sphere Outer Equator Plate Installation Completed (Artemis IV) – September 2019
- ✓ Pad LN2 Heat Exchanger GSE 60% Design Review (RL10 Chilldown) (Artemis IV) – Sept. 2019
- ✓ Pad B Emergency Egress System Design Started (Artemis II) – April 2019
- ✓ Pad B Environmental Control System Design Started (Artemis IV) – April 2019
- Converter Compressor Facility design complete, construction start (Artemis III) – June



Extensible Columns integrated with Side Flame Deflector



LH2 Upgrade Construction – The outer shell “equator” panels being assembled



Flame Trench/Deflector



Pad ECS TRR



Pad B ECS Testing



Extensible Columns Fabrication



Pad B ready for ML



Pad B Extensible Columns Testing



ML/Pad MEVV Complete



Pad ECS Testing


Multi-Payload Processing Facility (MPPF) (KSC)

Exploration Systems Development Update October 30, 2019


25

MPPF standalone V&V activities


- ✓ Hypergol Servicing/Deservicing V&V testing being split for Fuel and Ox Testing
 - ✓ Hyper-Fuel-Hot Flow V&V Completed – October 2018
 - ✓ Hyper-Oxidizer Hot Flow V&V Completed – September 2019
- ✓ MPPF ICPS Cold Flow Demonstration Completed – April 2019
- ✓ MPPF Hyper V&V Completed – September 2019
- ✓ MPPF Subsystem Standalone/Integrated V&V Completed – September 2019
- Spacecraft Offline System Acceptance Review / Operational Readiness Review – December 2019



Service Module Fuel Hot Flow



Crew Module Hot Flow De-servicing



Oxidizer Hot Flow



**MPPF V&V
Start**



**MPPF ICPS
Cold Flow
Demo**



**MPPF Hypergol
V&V**



**MPPF Subsystem
Standalone/
Integrated V&V**



**Spacecraft Offline
System Acceptance
Review**



**MPPF
Ready**

Spaceport Command & Control System (SCCS)


Exploration Systems Development Update October 30, 2019

26

- SCCS 6.0 – GFAS V&V
- SCCS 6.1 – GFAS Regression, Orion Flight Vehicle Processing, & ITCO
- SCCS 6.2 – GFAS Regression, WDR and Artemis I Launch



MPPF Hazardous Testing



MEVV @ VAB



MEVV @ Pad

- ✓ SCCS 6.0 Development Comp. – June 2019
- ✓ SCCS 5.0 Delta Sys S/W H/W Val Complete F1R (F1R Offline) – July 2019
- SCCS 6.0 V&V Comp. – December 2019
- SCCS 6.1 V&V Comp. – January 2020

☒ SCCS 5.0
Engineering
Release

☒ SCCS 5.0
Validated
Release

☒ SCCS 6.0
Development
Complete

☐ SCCS 6.0
System Test
Complete

☐ SCCS 6.0
Validated
Release

Ground Flight Application Software (GFAS)

Integrated Orion
Power-Up in
Firing Room 3



- ✓ ITL Run-for-Record 2 testing ECLSS, Avionics, GLS, Flight Communications, Navigation and Tracking, and Electrical Power System – September 2019
- Houston Orion Test Hardware (HOTH) test runs ECLSS, Avionics, Communication, Ground Launch Sequencer (GLS) – September thru October 2019
- ITL Run-for-Record 3 testing – December 2019 (post ITL blackout period)
- Cross Program initiatives are increasing, yielding positive results (FSW integration, Operations and Maintenance Requirements and Specifications (OMRS) scripting & pre test, Launch Commit Criteria / GLS algorithms, Green Run / Launch Countdown)

☒ GFAS
Drop 17

☒ GFAS Ready for
ML/Pad ME V&V

☐ GFAS Hoth Test
Runs

☐ GFAS ITL Test
Runs

☐ GFAS ITCO
Ready (SAR)

Exploration Systems Development: Systems Engineering & Integration

Wayne Jermstad

Acting Director, Cross-Program Systems Integration, Exploration Systems Development

SE&I Accomplishments This Quarter

Exploration Systems Development Update – October 30, 2019

28

- Developed ESD Internal Planning Manifest for Artemis I through Artemis IX (Sept)
- Baselined ESD 10045, ESD Architecture Configuration and Design Constraints (ACDC) (Sept)
- Held Integrated System and Mission Certification (ISMC) Dry Run #1 (Oct)
- Held Artemis II Sync Point #1 (Sept)
- Updated ESD 10030, Enterprise Functional Operational Capabilities (FOC) and Validation Expectations to Revision B (Sept)
- Updated ESD 10020, ESD CoFR Plan to Revision C to incorporate ESD Integration Review and ISMC (Sept)
- Completed EGS Validation testing Run for Record Test #1 in HOTH (HOTH-RFR-1) (Sept)
- Completed EGS Validation testing Run for Record Test #2 in ITL (ITL-RFR-2) (Oct)
- Completed EGS Integration Test #6 in SIL (Oct)
- ICAN Test 51b (Oct)
- ICAN Test 28b (Sept)

SE&I Schedule Assessment Teams

- Core Stage Assembly, Integration and Test (AI&T)
- Green Run Testing
- Vehicle Assembly, Integration and Test (AI&T)
- Integrated Loads and Guidance, Navigation and Control (GN&C)
- Integrated Trajectories
- Integrated Software
- Enterprise Verification and Validation

SE&I Issue Resolution Teams

- Range Safety (new)
- Pad Access/Con Ops
- Ignition Overpressure Sound Suppression (IOPSS) Water Flow Rate
- IT Security
- Block 1B Acoustics
- Block 1B Loads
- Imagery

Prep for FRR: ISMC Dry Run #1

Exploration Systems Development Update – October 30, 2019

31

- Purpose:
 - Assess and track the current state of flight readiness of the Enterprise from an integrated system and mission integration perspective
- Objectives:
 - Review the status of technical integration work necessary for Enterprise integration at the ESD Pre-FRR
 - Identify gaps in technical integration to allow appropriate time to address them
 - Identify technical integration issues that need to be addressed
 - Ensure integration issues have adequate plans for closure
 - Determine if any changes warranted to the agenda/content/presenters

Summary of ESD SE&I

Statement of Readiness (SoR) / Endorsement

- ✓ *Mission requirements defined and integrated (vertically and horizontally)*
- ✓ *Integrated flight and ground systems will function as designed; constraints identified*
- ✓ *Nonconformances, deviations, waivers, unexplained anomalies, etc. assessed / approved; residual risk acceptable*
- ✓ *Integrated flight and ground systems deemed acceptably safe; design hazard controls and FMEA/CIL rationale implemented*
- ✓ *Top risks address; residual risk acceptable*
- ✓ *Integrated PRA acceptable*
- ✓ *SE&I personnel trained and facilities certified*
- ✓ *External entities personnel, assets, services in place*
- ✓ *Plans and procedures in place to support all mission phases and will operate as designed*
- ✓ *Flight and ground systems environmental factors and constraints will maintain the integrated systems within design limits during all mission phases*
- ✓ *Mishap and contingency plans / procedures in place*
- ✓ *Compliance with NASA governance*

Stay Connected Between Committee Meetings

Exploration Systems Development Update – October 30, 2019

32





- [Space Launch System Mockup Arrives at Kennedy for Testing](#)
- [SLS Rocket Pathfinders Prepare Teams for One-of-a-Kind Hardware](#)
- [NASA Commits to Long-term Artemis Mission with Orion Production](#)
- [NASA Joins Last of Five Sections for Space Launch System Rocket](#)
- [Pad 39B Water Flow Test Comes Through Loud and Clear](#)

Sign up to get Moon to Mars updates from NASA:
<https://www.nasa.gov/specials/moon2mars/#five>

DEEP SPACE EXPLORATION SYSTEMS

PARTNERS & SUPPLIERS IN AMERICA



NASA's Deep Space Systems for human exploration are being built in all 50 states.





ESD Commonly Used Acronyms and Abbreviations

Exploration Systems Development Update – October 30, 2019

35

Acronym	Definition	Acronym	Definition	Acronym	Definition
AA	Ascent Abort	FRR	Flight Readiness Review	NDE	Nondestructive Evaluation
AI&T	Assembly, Integration, and Testing	FS	Forward Skirt	O&C	Operations and Checkout
APU	Auxiliary Power Unit	FSS	Flight Safety System	O/D	On Dock
ASEU	Aft Skirt Electrical Umbilical	FSW	Flight Software	OGV	Ogive Panel
ATLO	Assembly, Test, and Launch Operations	FWD	Forward	OMRS	Operations and Maintenance Requirements and Specifications
ATP	Authority to Proceed	GFAS	Ground/Flight Application Software	OMS-E	Orbital Maneuvering System Engine
BFS	Backup Flight System	GFAST	Ground/Flight Application Software Team	OSA	Orion Stage Adapter
C&DH	Command and Data Handling	GHe	Gaseous Helium	OTP	Orion Transportation Pallet
CAA	Crew Access Arm	GLS	Ground Launch Sequencer	PBS	Plum Brook Station
CM	Crew Module	GN2	Gaseous Nitrogen	PCDU	Power Control Distribution Unit
CMA	Crew Module Adapter	GNC	Guidance, Navigation, and Control	PDU	Power Distribution Unit
CMASS	Crew Module Ammonia Servicing Subsystem	GO2	Gaseous Oxygen	PLI	Propellant Liner Insulation
C/O	Check Out	GR&A	Ground Rules and Assumptions	PM	Program Manager
CR	Change Request	GRAS	Green Run Application Software	PPE	Power and Propulsion Element
CS	Core Stage	GRC	Glenn Research Center	PRA	Probabilistic Risk Assessment
CSI	Cross-Program Systems Integration	GSE	Ground Support Equipment	QD	Quick Disconnect
CSM	Crew and Service Module	HB	High Bay	QM	Qualification Motor
CSS	Consumable Storage System	HOTH	Houston Orion Test Hardware	RCS	Reaction Control System
CT	Crawler Transporter	HW	Hardware	SAR	System Acceptance Review
DCR	Design Certification Review	ICPS	Interim Cryogenic Propulsion Stage	SCCS	Spaceport Command and Control System
DFAT	Direct Field Acoustics Test	ICPSU	Interim Cryogenic Propulsion Stage Umbilical	SCAPE	Self-Contained Atmospheric Protection Ensemble
DVO	Detailed Verification Objectives	IPO	Initial Power On	SE&I	Systems Engineering and Integration
ECD	Estimated Completion Date	IT	Intertank	SIL	System Integration Lab
ECLSS	Environmental Control and Life Support System	ITCO	Integrated Test and Checkout	SITF	Software Integration Testing Facility
ECS	Environmental Control System	ITL	Integrated Test Laboratory	SLS	Space Launch System
ECU	Engine Controller Unit	JICB	Joint Integrated Control Board	SM	Service Module
EES	Emergency Egress System	JM	Jettison Motor	SSC	Stennis Space Center
EGS	Exploration Ground Systems	KCCS	Kennedy Complex Control System	SSPF	Space Station Processing Facility
EGSE	Electrical Ground Support Equipment	KSC	Kennedy Space Center	STA	Structural Test Article
EMI/EMC	Electromagnetic Interference and Electromagnetic Compatibility	LAS	Launch Abort System	SW	Software
ES	Engine Section	LCC	Launch Commit Criteria	TCU	Thermal Control Unit
ESA	European Space Agency	LETF	Launch Equipment Test Facility	TLM	Telemetry
ESD	Exploration Systems Development	LH2	Liquid Hydrogen	TPS	Thermal Protection System
ETE	End to End	LN2	Liquid Nitrogen	TRR	Test Readiness Review
FAST	Final Assembly and System Test	LO2	Liquid Oxygen	TSMU	Tail Service Mast Umbilical
EUS	Exploration Upper Stage	LOX	Liquid Oxygen	TVC	Thrust Vector Control
FCAS	Flight Controller Application Software	LVSA	Launch Vehicle Stage Adapter	ULA	United Launch Alliance
FCV	Flow Control Valve	MAF	Michoud Assembly Facility	V&V	Verification and Validation
FDIR	Fault Detection Isolation& Recovery	ME	Multi-Element	VAB	Vehicle Assembly Building
FIL	Fillet Panel	ML	Mobile Launcher	VAC	Vertical Assembly Center
FM	Flight Model	MPPF	Multi-Payload Processing Facility	WDR	Wet Dress Rehearsal
FMA	Final Mission Analysis	MPS	Main Propulsion System	XCS	Extensible Columns
FRAC	Flight Readiness Analysis Cycle	MSFC	Marshall Space Flight Center		